

Dated 14th May 1920.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 25th June 1920, for constructing a first class musafirkhana at Jog. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of July 1922.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. and 5 P.M., on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees five hundred and twenty in cash or Government Promissory notes, as earnest money, and be superscribed, "Tender for constructing a first class musafirkhana at Jog" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for constructing a 1st class musafirkhana at Jog, Sagar Taluk.

Items of work	Per	Quantity
Clearing site and levelling ground	Lump	sum
Earthwork excavating, foundation and filling in basement	C. yd.	103
Trapstone in mortar filling in foundation	C. ft.	2,776
Do basement and superstructure with joints, dressed	"	8,581
Coping over compound wall and pillars, stone	R. ft.	117
Chunam plastering	Sq.	116.71
Burnt stone slabs, dressed	S. ft.	639
Teakwood doors, battened shutters, etc., complete	"	455
Teakwood windows with iron bars and panelled shutters, etc., complete.	"	105
Teakwood gate with double shutters, etc., complete	Lump	sum
Teakwood wrought and put up	C. ft.	214.2
Teakwood eaves board	R. ft.	433
Roofing with 1st class Mangalore tiles on teak reepers, etc., complete.	Sq.	27.74
Ridge tiles set in mortar and pointed	R. ft.	193
Flooring with 1st class Mangalore tiles on 3" metal concrete and pointed.	Sq.	20.75
White and colourwashing	"	116.71
Tarring to wood work imbedded in masonry	"	15.00
Chocolate painting to doors, windows and eave boards	"	18.25
Date stone	Each.	1
Unforeseen and minor works, including finials, barge boards, drains, cisterns, gutters, etc.	Lump	sum

S. GOVINDA RAO,
For Executive Engineer.

MISCELLANEOUS DEPARTMENTS.
BANGALORE DISTRICT.

Notification.

In supersession to previous notifications, it is hereby notified for the information of the public that in accordance with Government Order No. 1275-324—G. F. 55-15-4, dated 30th August 1916, a Collecting Savings Bank has been opened in the Bangalore City, from 1st